

Appendix I – Summary of Erosion and Sediment Control Laws in the Canandaigua Lake Watershed

(Developed by the Canandaigua Lake Watershed Council.)

ZONING LAW AMENDMENT: STORMWATER CONTROL								
	STANDARDS AND MAINTENANCE							
	Technical Standards	Water Quality/ Quantity Standards	List of Standards or Stormwater Management Practices for Water Quality	Inspection Reports	Maintenance During Construction	Maintenance after Construction	Maintenance easement(s)	Maintenance Agreement
Sample Local Law	YES, "NYS SW Management Design Manual" and "NYS Standards and Specifications for Erosion and Sediment Control."	YES, no increase in turbidity.	YES	YES, applicant or developer or their representative shall inspect and document the effectiveness of all erosion and sediment control practices. Inspection reports shall be completed every 7 days and within 24 hours of any storm event producing 0.5 inches or precipitation or more. Reports shall be delivered to the Stormwater Management Officer.	YES, applicant or developer shall at all times properly operate and maintain all facilities of treatment and control. Sediment removed when design capacity is reduced by fifty (50) percent.	YES, permanent SW management practices shall be operated and maintained to achieve the goals of the law.	YES, for periodic inspection by municipality.	YES, legally recorded document that acts as a property deed restriction, and which provides for long-term maintenance of stormwater management practices.
City of Canandaigua	YES, "NYSDEC Stormwater Management Handbook" and old "NY Guidelines for Urban Erosion and Sediment Control."	YES, quality and quantity of runoff after development not substantially altered from pre-development conditions.	YES, detailed explanations of erosion control practices.	NO	YES, Stormwater Management and Erosion Control shall be a continuous process undertaken as necessary prior to, during, and after site preparation and construction.	YES, see "maintenance during construction."	YES, to permit the City to inspect, and if necessary, to take corrective action should the owner fail to properly maintain the system.	NO

Town of Canandaigua	YES, Old "NY Guidelines for Urban Erosion and Sediment Control."	NO	NO	NO	YES, the control of erosion and sediment shall be a continuous process undertaken as necessary prior to, during, and after site preparation and construction.	YES, see "maintenance during construction."	NO	NO
Town of Middlesex	YES, Old "NY Guidelines for Urban Erosion and Sediment Control" and "Reducing the Impacts of Stormwater Run-off."	YES, quality and quantity of runoff after development not substantially altered from pre-development conditions.	NO	NO	NO	YES, the Town shall determine whether stormwater management facilities are to be maintained by the developer/owner, a homeowner's association, or by the Town.	YES, in order to permit the Town Code Enforcement Officer to inspect and, if necessary, to take corrective action should the owner fail to properly maintain the system.	NO
Town of Gorham	NO	NO	YES, somewhat detailed explanations of erosion control practices.	NO	YES, the control of erosion and sediment shall be a continuous process undertaken as necessary prior to, during, and after site preparation and construction.	YES, erosion or sediment control devices shall be maintained as necessary to provide adequate protection against erosion and sediment and to insure long term performance.	NO	NO